GRAPHIC PANEL A

Hybrid Pro Rental Kit:
Hybrid Pro Modular Kit 03

Dye Sub Graphic Panels A
Total Graphic Area: 39.3125”w x 86.5625”h
Finished Graphic Area: 35.3125”w x 82.5625”h

Dye Sub Graphic Panels B
Total Graphic Area: 27.5”w x 74.75”h
Finished Graphic Area: 23.5”w x 70.75”h

Dye Sub Graphic Panels C
Total Graphic Area: 51.125”w x 98.375”h
Finished Graphic Area: 47.125”w x 94.375”h

Dye Sub Graphic Panels D top -
(1) print at:
Total Graphic Area: 64.75”w x 21.75”h
Finished Graphic Area: 60.75”w x 17.75”h
(1) print at:
Total Graphic Area: 65.9375”w x 21.75”h
Finished Graphic Area: 61.9375”w x 17.75”h

Dye Sub Graphic Panels D side -
(1) print at:
Total Graphic Area: 21.75”w x 94”h
Finished Graphic Area: 17.75”w x 90”h
(1) print at:
Total Graphic Area: 21.75”w x 92.5875”h
Finished Graphic Area: 17.75”w x 88.875”h

Please be sure to include a 2” bleed around the perimeter of the center graphic.

Please consider obstructions and spaces created by the extrusions when designing your graphics.

General Art Guidelines:

- CMYK Color Mode
- All Solid Coated Pantone colors should be called out in the art as spot colors
- Embed all images and support files
- Resolution must be 100-120 ppi
- All fonts must be created to outlines
- Do not scale artboard
- Background color/images must bleed to the edge of artboard
- Do not use spot colors from template in your artwork as they will not print

GRAPHIC PANEL B

GRAPHIC PANEL C (Backlit)

bleed area
trim line
safe zone

90” height + bleed

GRAPHIC PANEL D (Side Outside)

GRAPHIC PANEL D (Side Inside)

GRAPHIC PANEL D (Top Inside)

GRAPHIC PANEL D (Top Outside)